

DPX Cabinet Frames

All frames are supplied with two pairs of numbered universal mounting rails, levelers, a bag of 40 M6 clip nuts with screws and casters to make moving the frame easy. Cabinets should always be leveled on site. Two 4" x 4" Cable Managers come standard with each cabinet; these may be upgraded to 6" or 8" Cable Managers.

DLC will pre-configure your cabinet with shelves, cable boxes and ground bars to your specifications.

We can also source and install other peripheral components that you require such as I/E patch panels, UPS, PDU etc.

The 31" wide cabinet accommodates 4" wide cable boxes. These come in 3 depths; 4", 6" and 8". The universal mounting rails come equipped with cable entry holes as shown on the cable management page.

CABINET	DEPTH "A"	OVERALL HEIGHT "B"	# OF RACK UNIT "C"
DPX325230-19	30"	58 ¾"	30
DPX326130-19	30"	67 ½"	35
DPX327030-19	30"	76 ¼"	40
DPX327730-19	30"	83 ¼"	44
DPX328430-19	30"	90 ¼"	48
DPX365230-19	34"	58 ¾"	30
DPX366130-19	34"	67 ½"	35
DPX367030-19	34"	76 ¼"	40
DPX367730-19	34"	83 ¼"	44
DPX368430-19	34"	90 ¼"	48
DPX425230-19	40"	58 ¾"	30
DPX426130-19	40"	67 ½"	35
DPX427030-19	40"	76 ¼"	40
DPX427730-19	40"	83 ¼"	44
DPX428430-19	40"	90 ¼"	48

